

DNREC Division of Watershed Stewardship 285 Beiser Boulevard, Suite 102 Dover, DE 19904 (302) 739-9921

Office Use Only	
Date Received:	
Meeting date/time	
Stormwater Assessment Study (SAS) Checklist	
Project Name: Bridgeville PODS Storage Facility	
Owner/Developer Name: FED Investments	
Contact Person: Gary Krupnick	
e-mail: gpk33fly@aol.com	Phone: 631-435-1818
Consultant Company: Axiom Engineering, LLC	
Contact Person: Ken Christenbury, P.E.	
e-mail: ken@axeng.com	Phone: 302-855-0810
Check all items that apply; leave check box blank if N/A.  A. Documents  Items should be arranged in the following order:  ☐ This completed Stormwater Assessment Study (SAS) Checklist  ☐ Brief narrative to include the following:  ■ Project type/description  ■ Description of soil limitations and how they relate to BMP selection  ■ Applicable criteria if the site is in an area served by Watershed Master Plan  ■ Impacts to tax ditch watershed or ROW  ■ Description of existing site conditions and proposed conditions including information on downstream conveyance and Points of Analysis (POAs)  ■ Identify and describe existing drainage structures and features  ■ Provide photographs of structures / channels / outfalls / POAs  ☐ Feedback from DeIDOT Maintenance regarding drainage concerns (if relevant).  Consultant to contact DeIDOT to determine if there are any known drainage problems.  Provide Parcel ID number and a description of the project location, from the nearest intersection. DeIDOT will respond with any known drainage and flooding problems.  ● New Castle County − (302) 326-4523  ● Kent County − (302) 760-2424  ● Sussex County − (302) 853-1340	
<ul> <li>B. Existing Hydrology Mapping Submit an existing drainage features map based on field-run topo or current LIDAR data: ☑ On-site subareas ☑ Off-site subareas ☑ Site points of analysis</li> </ul>	

### C. Stormwater Assessment Study GIS Mapping

Provide maps from the following SAS GIS Web application link:

https://firstmap.delaware.gov/sasgis

(Layers to be overlaid on the most recent aerial imagery basemap)

- ✓ Site location
- Parcel Boundary showing parcel and ID
- ✓ NHD rivers, streams and water features
- Contours
- ☑ Tax Ditch Mapping (watershed boundaries, channel locations, rights-of-way)
- ✓ Wellhead protection
- Aquifer recharge areas
- ✓ Land Use / Land Cover (LULC)
- ✓ Soils
- ✓ State Wetland Mapping Project (SWMP)
- ✓ Head of Tide Mapping
- ✓ Potential Contamination Sources
  - ✓ SIRB Sites
  - Leaking Tanks
  - Above Ground Storage Tank Facility
  - Underground Storage Tanks
  - ✓ Solid and Hazardous Waste Site
- ☑ Flood Data (BFE and FEMA Flood Map)
- ✓ Depth to Water WET

### D. Supplemental Information

- StreamStats Map and Basin Characteristics Report showing limit of downstream analysis. (The downstream analysis point will be located at the point in the watershed where the site area comprises less than 10% of the watershed area. Alternative downstream limit points may be shown for discussion.)
  - StreamStats link: https://streamstats.usgs.gov/ss

#### Adjacent well locational data

Well permit data can be searched by tax parcel ID from the Delaware OpenData portal: <a href="https://data.delaware.gov/Energy-and-Environment/Well-Permits/2655-qn8i">https://data.delaware.gov/Energy-and-Environment/Well-Permits/2655-qn8i</a>

- ✓ Public wells within 150' of parcel boundary
- ✓ Domestic wells within 100' of parcel boundary
- Adjacent septic system data
  - ☑ Drainfields within 50' of parcel boundary
  - System components within 25' of parcel boundary

This checklist is for guidance only. The Delegated Agency reserves the right to request additional information during the review process as it deems necessary. Compliance with the checklist in no way is meant to relieve the design professional of his/her professional responsibilities.



18 Chestnut Street Georgetown, DE 19947 www.axeng.com Phone: 302 855-0810
Fax: 302 855-0812
E-mail: axiom@axeng.com

April 22, 2022

Sussex Conservation District 20728 N. DuPont Blvd. - Suite 317 Georgetown, DE 19947

Attn: Donna Colton/John Justice - Sediment and Stormwater Reviewer

RE: 0579-2201 PODS of Bridgeville - Step 1 SAS

Sussex Co. TM

Dear Ms. Colton / Mr. Justice:

Please find attached the Step 1 Stormwater Assessment Study for the above referenced site.

#### INTRODUCTION

This report is prepared to support the design of the development of a PODS Storage Facility in the town of Bridgeville. The developer proposes the construction of a 60,300 s.f. warehouse. The narrative is prepared to support the general approach for controlling stormwater runoff generated by proposed additions.

#### GENERAL SITE INFORMATION

#### **Existing Site**

The subject site is located on the northbound side of South Mainstreet and is bordered with the Lands of Anice Lynn Kulp and David Doane. The property is bounded by US Route 13, Rifle Range Road, South Main Street. Currently the parcel is used for agricultural cultivation. The entire property is 13.72 ± acres, the developer is proposing subdividing approximately 5-6 acres from the S. Main Street frontage for the project. The subject parcel will not have frontage on Route 13 or Rifle Range Road. The overall LOD for the project, including DelDOT right of way improvements, is 6± acres.

Based on the USDA - Natural Resources Conservation Service - Web Soil Survey, the site (area of development) consists of Hambrook sandy loam (HbA), 2-5% slopes, Mid-Atlantic Coastal Plain.



Drainage area 1 encompasses the west side of the parcel. Drainage from this area drains towards an existing ditch that drains towards the south and offsite. This drainage area contains slopes from 12%, based on the existing topographic data. Drainage area 1 is  $\pm 3.65$  acres, including the Main Street R.O.W. and portions of the adjacent parcel to the north.







Drainage area 3 drains towards the swale along U.S. Route 13 and then moves south off site. This drainage area contains slopes from 1-2%, based on the existing topographic and lidar contour data. Drainage area 3 is 15.97 acres. Drainage area 2 makes up the portion of Drainage area 3 that is located on-site. Drainage area 2 is  $\pm 4.23$  acres. Drainage area 2 will be routed to the site's infiltration basin and will be removed from outfall.



### **Developed Site**

The improvements proposed on site include the construction of a 60,300 s.f. POD Storage facility, parking area, landscaped berm, utility, and other site improvements. The overall site will be collected via a closed pipe storm sewer system discharging to an infiltration facility designed to infiltrate the CV event. FV storm flows will have an overflow pipe discharging into the Main Steet road-side swale, managed to predeveloped peak discharges. Remaining areas outside of the site development will discharge offsite, overland and uncontrolled as it currently does.

**Soil Conditions** 

GTA has obtained soil borings and run infiltration test in the location of the proposed infiltration basin. The site is marginally suited for infiltration. Infiltration will be used for the RPV and perhaps the CV storm events. The FV will be designed to overflow into the Main Street road-side ditch. A copy of the GTA report is included in this submittal.

Please do not hesitate to contact me if you have any further questions or comments.

Sincerely,


Kenneth R. Christenbury, P.E. President, Axiom Engineering, LLC



# 1.0-SITE




11/29/2021, 4:39:09 PM



# 2.0 - PARCEL BOUNDARY




11/29/2021, 4:39:41 PM






## 3.0 - NHD WATER FEATURES




11/29/2021, 4:40:39 PM


Watersheds

FlowLine





### 4.0 - CONTOUR






<all other values>







# 5.0 - TAX DITCH MAPPING



11/29/2021, 4:42:37 PM



# 6.0 - WELL HEAD PROTECTION



11/29/2021, 4:43:25 PM

